

# Product Technical Specification

KS-PTS-2026-V1.2 | 29 September 2026 | Brand v1.4

|                      |                                                             |
|----------------------|-------------------------------------------------------------|
| Document Ref         | KS-PTS-2026-V1.2                                            |
| Version / Issue Date | V1.2   29 September 2026                                    |
| Document Owner       | KAISTEEL LIMITED (Hong Kong)                                |
| Product Family       | Modular Outdoor Kitchen Systems                             |
| Status               | Controlled Commercial Draft - Project Confirmation Required |

**CONTROL RULE** This specification does not authorize manufacture by itself. Each order requires an approved model, bill of materials (BOM), shop drawing, utilities schedule and Technical Freeze Sheet. Any item marked TBC must be confirmed in writing before production release.

## 1. Purpose, Scope and Document Hierarchy

This document defines the technical boundary for KAISTEEL modular outdoor kitchen systems supplied for residential or commercial B2B projects. It is intended for quotation review, technical approval, manufacturing coordination, pre-shipment inspection, installation planning and warranty traceability.

|                            |                                                                                                                                                                                                                                                             |
|----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Included                   | Primary structure, exterior and interior panel systems, cabinet modules, countertop and sink, canopy or shutter mechanism, configured electrical/lighting provisions, configured plumbing provisions, selected appliances, finish and export packaging.     |
| Not automatically included | Site foundations, local structural engineering, utility connection, gas commissioning, destination permits, local installation, lifting/unloading, import clearance, certification testing, or third-party appliances unless expressly listed in the order. |
| Order of precedence        | Signed sales contract / PI -> approved Technical Freeze Sheet -> approved shop drawings and BOM -> this specification -> catalog and other marketing materials.                                                                                             |
| Conflict rule              | Where documents conflict, production shall stop and KAISTEEL shall issue a written clarification or revision. Marketing images and renderings are illustrative and do not override approved technical documents.                                            |

## 2. Product Identification and Approved Configuration

|                        |                                 |
|------------------------|---------------------------------|
| Customer / Distributor | _____                           |
| Project / Site         | _____                           |
| PO / PI Number         | _____                           |
| Model / Series         | _____                           |
| Serial Number(s)       | Assigned before final QC: _____ |

|                        |                                                      |
|------------------------|------------------------------------------------------|
| Use Classification     | Residential [ ] Commercial [ ]                       |
| Approved Drawing / BOM | Drawing Rev: _____ BOM Rev: _____ Freeze Date: _____ |

## 2.1 Commercial model reference

| Model       | Commercial Series | Nominal Envelope     | Closure / Canopy                 | Control Status                                                 |
|-------------|-------------------|----------------------|----------------------------------|----------------------------------------------------------------|
| KS-E2300    | Essential         | 2300 x 880 x 2400 mm | Manual closure / canopy          | Dimensions and final configuration subject to approved drawing |
| KS-P2300    | Professional      | 2300 x 880 x 2400 mm | Electric actuator lift-up canopy | Actuator and control data TBC by project                       |
| KS-P2900    | Premium           | 2900 x 880 x 2400 mm | Electric actuator lift-up canopy | Appliance and entertainment package by BOM                     |
| KS-R2900    | Premium Enclosed  | 2900 x 960 x 2400 mm | Electric roller shutter          | Shutter and interlock data TBC by project                      |
| KS-P2900-UP | Premium Upgraded  | 2900 x 960 x 2400 mm | Electric actuator lift-up canopy | Deep-worktop configuration by approved drawing                 |

IMPORTANT Published weights, packed volumes and container quantities differ across current source materials. These figures are not controlled generic values. Gross/net weight, packed dimensions and loading quantity shall be measured and recorded for each approved model before shipment.

## 3. System Construction and Materials

Different components use different materials according to structural, functional and environmental requirements. The complete product is not made entirely from stainless steel. For applicable stainless-steel components, 304 is the standard option; 316 options are recommended for coastal and high-corrosion environments, subject to project confirmation. Final component materials, grades and construction shall be confirmed in the approved project BOM and drawings.

| System                         | Controlled Requirement                                                                                                                 | Project / Manufacturer Confirmation                                                                     |
|--------------------------------|----------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|
| Primary frame                  | Structural frame material and corrosion protection per approved project BOM.                                                           | Material grade, section sizes, wall thickness, corrosion protection, weld standard and load basis: TBC. |
| Exterior panels                | Panel material and finish suitable for the approved outdoor application, per project BOM.                                              | Material, grade, thickness, finish system and fixing details: TBC.                                      |
| Cabinet core / interior panels | Cabinet body, doors and interior/core construction as specified in the approved project BOM; material selection is component-specific. | Face material and grade, thickness, any core/fill material, adhesive/fire data and exact scope: TBC.    |
| Water-resistant layers         | SPC or other water-resistant layers only where shown on the approved BOM/drawing.                                                      | Material grade, thickness and location: TBC. No blanket claim applies.                                  |

| System             | Controlled Requirement                                                                  | Project / Manufacturer Confirmation                                            |
|--------------------|-----------------------------------------------------------------------------------------|--------------------------------------------------------------------------------|
| Base / floor       | Base construction and anchoring arrangement per approved project drawing.               | Board/material type, thickness, live load, point load and anchoring: TBC.      |
| Fasteners          | Corrosion-resistant fasteners compatible with connected materials and outdoor exposure. | Material grade, coating and torque schedule: TBC.                              |
| Sealants / gaskets | Outdoor-compatible sealants and gaskets at designated joints and penetrations.          | Brand/type, UV resistance, food-zone suitability and service temperature: TBC. |

### 3.1 Worktop and sink

|                             |                                                                                                                                                                                                                                                                                                                    |
|-----------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Worktop material            | 304 is the standard option for applicable stainless-steel worktop components; 316 options are recommended for coastal and high-corrosion environments, subject to project confirmation. Confirm grade and construction in the BOM. Material certificate / supplier declaration required for each production batch. |
| Nominal thickness options   | 6 mm / 8 mm / 10 mm. The selected thickness must be stated in the BOM and approved drawing.                                                                                                                                                                                                                        |
| Official texture names      | Sand Time   Floating Light   Cracked Realm   Mystic Engrave   Infinity.                                                                                                                                                                                                                                            |
| Texture process             | TBC by manufacturer for each texture. Marketing names do not define the manufacturing process.                                                                                                                                                                                                                     |
| Edges / openings / upstands | As shown on the approved shop drawing. Edge profile, radius, cut-outs, drainage falls, rear/side upstands and tolerances must be dimensioned.                                                                                                                                                                      |
| Sink                        | Factory-integrated or installed stainless steel sink as listed in the BOM. Stainless grade, gauge, dimensions, waste fitting, faucet and overflow: TBC by project.                                                                                                                                                 |
| Finish acceptance           | Uniform approved texture and direction; no structural cracks, sharp edges, unacceptable dents, deep scratches, contamination or visible repair outside the approved sample standard.                                                                                                                               |

### 3.2 Cabinetry, storage and hardware

|                   |                                                                                                                                                         |
|-------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------|
| Cabinet modules   | Component-specific materials and cabinet construction as listed in the approved BOM. No blanket all-stainless-steel or fixed core construction applies. |
| Doors and drawers | Free movement, controlled gaps, positive latching and no interference through full travel.                                                              |
| Hardware          | Outdoor-suitable hinges, slides, handles and locking parts; make, grade, load rating and corrosion class: TBC.                                          |
| Shelving          | Integrated organizational shelving only where listed in the BOM; load rating: TBC.                                                                      |
| Color             | Standard commercial references: black, white/gray or silver variants. Exact color code, gloss and approved sample govern production.                    |

## 4. Canopy, Shutter and Mechanical Systems

| Item                    | Requirement                                                                                      | Acceptance / Data Required                                                                           |
|-------------------------|--------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------|
| Manual mechanism        | Smooth controlled movement and secure retention at intended positions.                           | Operating force, retention method, cycle test and safety provision: TBC.                             |
| Electric lift canopy    | Electric actuator system matched to load and travel; controls located and protected as approved. | Actuator make/model, voltage, stroke, load, duty cycle, IP rating, limit protection and wiring: TBC. |
| Electric roller shutter | Complete opening/closing without binding; secure in closed state.                                | Motor, rated load, controls, limit settings, manual override, interlock and IP rating: TBC.          |
| Hinges / pivots         | Aligned, securely fixed and free from abnormal play or noise.                                    | Material, fastener grade, lubrication and torque: TBC.                                               |
| Pinch / crush risk      | Moving systems shall include project-approved safeguards, warnings and operating instructions.   | Risk assessment and destination requirements: project responsibility / TBC.                          |
| Functional cycle test   | Minimum factory cycle test before shipment.                                                      | Cycle quantity: TBC; record actual test in QC checklist.                                             |

## 5. Electrical and Lighting

**NO IMPLIED CERTIFICATION** Electrical components and assemblies are project-specific. CE, UKCA, UL, ETL, CSA, RCM or other certification shall not be claimed unless a valid certificate and exact model/scope are recorded in the order file.

|                           |                                                                                                                                                                                     |
|---------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Supply                    | Voltage, frequency, phase, plug/connection, rated input and maximum current: TBC for destination and project.                                                                       |
| Distribution / protection | Outdoor distribution box and protective devices only as stated in BOM. RCD/GFCI/RCBO rating, breaker schedule and enclosure IP rating: TBC.                                         |
| Earthing / bonding        | Protective earthing and equipotential bonding points to be provided where required by the approved electrical design and destination rules.                                         |
| Wiring                    | Cable type, conductor size, temperature rating, routing, strain relief, terminals, glands and separation from heat/water zones: TBC.                                                |
| Lighting                  | Recessed and/or LED ambient lighting as configured. Color temperature, power, driver, dimming and IP rating: TBC.                                                                   |
| Sockets / track power     | Quantity, type, rating and destination compatibility per BOM. Covers and outdoor suitability shall be confirmed.                                                                    |
| Factory test              | Visual wiring inspection, continuity, protective-earth continuity, insulation resistance and functional checks as applicable. Test limits and instrument details shall be recorded. |
| Site connection           | Final connection, inspection and certification by a qualified person under destination requirements unless expressly included in KAISTEEL scope.                                    |

## 6. Plumbing, Drainage and Gas Interfaces

| Interface         | Factory Scope                                                                     | Project Confirmation / Site Responsibility                                                              |
|-------------------|-----------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|
| Cold / hot water  | Internal pipework and prepared connection only where listed in BOM.               | Pipe material/size, pressure rating, inlet size/location, hot-water provision and pressure test: TBC.   |
| Waste             | Sink waste and internal drainage arrangement where configured.                    | Outlet size/location, trap, fall, venting and local connection: TBC.                                    |
| Leak testing      | Factory leak test where internal plumbing is supplied.                            | Test medium, pressure/duration and acceptance limit: TBC; record in QC.                                 |
| Gas appliance     | Appliance and flexible/internal connection only if expressly listed and approved. | Fuel type, inlet pressure, regulator, hose/pipe standard, shut-off, ventilation and certification: TBC. |
| Gas commissioning | Not included unless expressly agreed.                                             | Must be completed by a qualified local gas installer in accordance with destination requirements.       |

## 7. Appliances and Optional Equipment

|                            |                                                                                                                                                                               |
|----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Configuration basis        | All grills, cooktops, range hoods, refrigerators, displays/TVs, speakers and other equipment must be identified by manufacturer, model and quantity in the BOM.               |
| Typical commercial options | 4- or 6-burner gas/charcoal grill, induction cooktop, range hood, refrigerator, entertainment display and outdoor audio. Typical descriptions are not a commitment of supply. |
| Compatibility              | Dimensions, ventilation clearances, heat shielding, electrical/gas requirements, service access and destination suitability shall be checked before Technical Freeze.         |
| Certificates               | Copy exact manufacturer declarations/certificates into the order file where required. Certificate scope must match the supplied model.                                        |
| Warranty                   | Third-party appliances are covered solely by the appliance manufacturer's warranty unless the signed contract expressly states otherwise.                                     |

## 8. Environmental and Installation Conditions

| Condition              | Requirement / Limitation                                                                                                                                                                   |
|------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Outdoor exposure       | Product is designed for configured outdoor use but is not represented as permanently watertight or flood-proof. Close the canopy/shutter and follow the maintenance guide when not in use. |
| Coastal / saline sites | Enhanced cleaning and corrosion-control measures are required. Material/finish selection and maintenance interval must be project-reviewed.                                                |
| Wind                   | Site wind load, anchoring, closed/open operating limits and local structural compliance are not established by this generic specification; project engineering is required.                |

| Condition                    | Requirement / Limitation                                                                                                                             |
|------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------|
| Temperature / snow / seismic | Design values and suitability are TBC by project and destination.                                                                                    |
| Foundation                   | Level, stable, adequately drained and capable of supporting verified equipment and imposed loads. Tolerances and anchor layout per approved drawing. |
| Clearances                   | Maintain appliance manufacturer clearances, ventilation and service access. Do not obstruct drainage or electrical ventilation.                      |
| Installation                 | Assembly, lifting, anchoring and utility connection by qualified personnel using approved instructions and local requirements.                       |

## 9. Surface Finish, Workmanship and Dimensional Control

| Characteristic         | Default Acceptance Principle                                                                                     | Project-specific Value                  |
|------------------------|------------------------------------------------------------------------------------------------------------------|-----------------------------------------|
| Overall dimensions     | Measured against approved drawing; no interference with installation or operation.                               | Tolerance: TBC                          |
| Level / squareness     | Stable, square and visually aligned; doors, drawers and moving systems operate freely.                           | Tolerance: TBC                          |
| Panel gaps / flushness | Consistent with approved sample and drawing.                                                                     | Tolerance: TBC                          |
| Welds                  | Complete and structurally sound; no visible cracks, burn-through, sharp spatter or unapproved repair.            | Weld process / acceptance standard: TBC |
| Coating / panel finish | Uniform approved color/gloss; free from peeling, blistering, exposed substrate and unacceptable dents/scratches. | Color code, gloss and DFT: TBC          |
| Stainless texture      | Correct official texture, uniform orientation and approved appearance.                                           | Approved sample / finish ID: TBC        |
| Sharp edges            | No accessible hazardous sharp edges or burrs after normal assembly and use.                                      | Mandatory                               |

## 10. Factory Inspection, Traceability and Release

|                   |                                                                                                                                                                      |
|-------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Traceability      | Each completed unit shall carry a unique Serial Number linked to PO/PI, model, drawing/BOM revisions, material records, inspection date, inspector and photo record. |
| Inspection basis  | The current KAISTEEL Pre-Shipment Quality Inspection Checklist V1.1, approved project documents and applicable supplier test records.                                |
| Material evidence | Retain SUS304/SUS316 evidence (as ordered), structural material declarations and finish/batch data reasonably available for the order.                               |
| Nonconformity     | Safety, structural, functional, identity or missing-part failures place the unit on HOLD. Rework requires documented reinspection.                                   |

|               |                                                                                                                                    |
|---------------|------------------------------------------------------------------------------------------------------------------------------------|
| Final release | Only an authorized KAISTEEL representative may release the unit after inspection status is PASS and required evidence is complete. |
|---------------|------------------------------------------------------------------------------------------------------------------------------------|

## 11. Packaging, Marking and Shipping Data

| Item                   | Controlled Requirement                                                                                                                                       |
|------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Protection             | Clean and dry product; protect stainless surfaces, corners, projecting parts, moving components, glass/screens and appliances against handling and moisture. |
| Restraint              | Lock or brace doors, drawers, canopy/shutter and loose components. Prevent movement inside the package.                                                      |
| Packaging              | Standard export protection plus crate/frame where ordered. Wood packaging must meet destination requirements, including ISPM 15 where applicable.            |
| Marking                | PO/PI, model, Serial Number, case number, gross/net weight, dimensions, center of gravity/handling marks and destination marks as required.                  |
| Measured shipping data | Record actual packed L x W x H, gross/net weight and package count. Do not rely on historical catalog estimates.                                             |
| Document pack          | Packing list, commercial invoice, approved QC release, photo record, installation/operation documents, warranty information and applicable certificates.     |

## 12. Warranty Alignment

|                                                 |                                                                                                                                                                                                                                                                                                                                                           |
|-------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Primary structure                               | Residential: 15-Year Limited   Commercial: 15-Year Limited. Worktop, cabinet body and doors, and structural frame as supplied under the approved order and BOM; defects in material and workmanship only. Component materials and construction are project-specific; no all-stainless-steel construction is implied. Subject to the Warranty Certificate. |
| Surface finish                                  | Residential: 5-Year Limited   Commercial: 5-Year Limited. Natural weathering, fading and surface oxidation are excluded as stated in the Warranty Certificate.                                                                                                                                                                                            |
| Mechanical and electrical functional components | 1 Year for residential and commercial use, including configured actuators, canopy motors and LED lighting systems.                                                                                                                                                                                                                                        |
| Third-party appliances                          | Manufacturer Warranty only.                                                                                                                                                                                                                                                                                                                               |
| Governing document                              | KAISTEEL Limited Warranty Certificate V1.3 (KS-WC-2026-V1.3), or a later certificate expressly incorporated into the signed order. This specification does not expand warranty coverage.                                                                                                                                                                  |

### 13. Project Confirmation Schedule

| Required Before Production Release                | Value / Reference | Status / Approval     |
|---------------------------------------------------|-------------------|-----------------------|
| Final model, dimensions and layout                | _____             | Open [ ] Approved [ ] |
| Drawing and BOM revision                          | _____             | Open [ ] Approved [ ] |
| Frame sections, thickness and corrosion system    | _____             | Open [ ] Approved [ ] |
| Countertop thickness, texture and edge details    | _____             | Open [ ] Approved [ ] |
| Panel materials, thickness and finish code        | _____             | Open [ ] Approved [ ] |
| Canopy/shutter mechanism and controls             | _____             | Open [ ] Approved [ ] |
| Electrical schedule and destination compatibility | _____             | Open [ ] Approved [ ] |
| Water, drainage and gas interfaces                | _____             | Open [ ] Approved [ ] |
| Appliance make/model/certification                | _____             | Open [ ] Approved [ ] |
| Packaging, measured shipping data and marks       | _____             | Open [ ] Approved [ ] |

### 14. Approval and Change Control

VERSION CONTROL A signed approval does not authorize unrecorded substitutions. Any change after Technical Freeze requires a written Engineering Change Order describing the technical, price and delivery effect.

| Role                            | Name / Company | Signature | Date  |
|---------------------------------|----------------|-----------|-------|
| Prepared by                     | KAISTEEL       | _____     | _____ |
| Technical review                | _____          | _____     | _____ |
| Manufacturer confirmation       | _____          | _____     | _____ |
| Customer / Distributor approval | _____          | _____     | _____ |